VICTORIA THEATER REDEVELOPMENT PROJECT

Draft Environmental Impact Statement

Lead Agency:
Empire State Development

Project Sponsor:
Harlem Community Development Corporation

Applicant:
Danforth Development Partners, LLC

Prepared by:
AKRF, Inc.

July 2012

VICTORIA THEATER REDEVELOPMENT PROJECT
DRAFT ENVIRONMENTAL IMPACT STATEMENT (DEIS)

Project Location:	237 West 125th Street New York, NY 10027 Block 1931, Lot 17 Manhattan Community District 10
Lead Agency:	Empire State Development 633 Third Avenue, 34th Floor New York, NY 10017
Lead Agency Contact:	Rachel Shatz Vice President, Planning & Environmental Review
Project Sponsor:	Harlem Community Development Corporation
Project Applicant:	Danforth Development Partners, LLC
Preparer:	AKRF, Inc. 440 Park Avenue South New York, NY 10016

Copies of the DEIS are available for review at Empire State Development. A public hearing on the DEIS will be held at a date and location to be announced; the Lead Agency will publish a notice of the hearing at least 14 days before it takes place and will accept written comments for at least 10 days following the close of the hearing.

Table of Contents

Executive Summary **S-1**

1: Project Description **1-1**
A. Identification of the Proposed Project 1-1
B. Project Purpose and Need 1-2
C. Development History 1-3
D. Description of Proposed Project 1-3
Existing Conditions On the Project Site 1-3
Proposed Development Program 1-4
Proposed Design and Restoration 1-5
E. Proposed Actions 1-7
F. Framework for Analysis 1-7
Scope of Environmental Analysis 1-7
Analysis Year 1-8
Definition of Study Areas 1-8
Defining Baseline Conditions 1-8
G. Environmental Review Process 1-9
Process Overview 1-9
Coordination With Other Review Processes 1-10

2: Land Use, Zoning, and Public Policy **2-1**
A. Introduction 2-1
Principal Conclusions 2-1
B. Background and Development History 2-1
C. Existing Conditions 2-2
Land Use 2-2
Zoning 2-3
Public Policy 2-6
D. The Future Without the Proposed Project 2-8
Land Use 2-8
Zoning and Public Policy 2-9
E. Probable Impacts of the Proposed Project 2-10
Land Use 2-10
General Project Plan and Zoning 2-11
Public Policy 2-13

3: Socioeconomic Conditions **3-1**

4: Community Facilities and Services **4-1**

5: Open Space 5-1
A. Introduction 5-1
Principal Conclusions 5-1
B. Methodology 5-2
Direct Effects Analysis 5-2
Indirect Effects Analysis 5-2
C. Preliminary Assessment 5-5
Existing Conditions 5-5
The Future Without the Proposed Project 5-9
Probable Impacts of the Proposed Project 5-10

6: Shadows 6-1
A. Introduction 6-1
B. Definitions and Methodology 6-2
Definitions 6-2
Methodology 6-2
C. Preliminary Screening Assessment 6-3
Tier 1 Screening Assessment 6-3
Tier 2 Screening Assessment 6-3
Tier 3 Screening Assessment 6-4
D. Detailed Shadow Analysis 6-5
Resources of Concern 6-6
Resources That Would Not Experience Incremental Shadow 6-7
March 21/September 21 6-7
May 6/August 6 6-7
June 21 6-8
December 21 6-8
E. Conclusions 6-8

7: Historic and Cultural Resources 7-1
A. Introduction 7-1
Principal Conclusions 7-1
B. Methodology 7-2
Archaeological Resources 7-2
Architectural Resources 7-3
C. Existing Conditions 7-4
Archaeological Resources 7-4
Architectural Resources 7-4
D. The Future Without the Proposed Project 7-11
Project Site 7-11
Study Area 7-11
E. Probable Impacts of the Proposed Project 7-11
Archaeological Resources 7-11
Architectural Resources 7-11

8: Urban Design and Visual Resources 8-1
A. Introduction 8-1
Principal Conclusions 8-1

B. Preliminary Assessment 8-2
C. Methodology 8-3
D. Existing Conditions 8-3
Urban Design 8-3
Visual Resources 8-6
E. The Future Without the Proposed Project 8-7
Project Site 8-7
Study Area 8-7
F. Probable Impacts of the Proposed Project 8-7
Urban Design 8-7
Visual Resources 8-9

9: Natural Resources 9-1

10: Hazardous Materials 10-1
A. Introduction 10-1
Principal Conclusions 10-1
B. Existing Conditions 10-2
Subsurface Conditions 10-2
Hazardous Materials Assessment 10-2
C. The Future Without the Proposed Project 10-3
D. Probable Impacts of the Proposed Project 10-3

11: Water and Sewer Infrastructure 11-1
A. Water Supply 11-1
B. Wastewater and Stormwater Conveyance and Treatment 11-1

12: Solid Waste and Sanitation Services 12-1

13: Energy 13-1

14: Transportation 14-1
A. Introduction 14-1
B. Project Trip Generation 14-2
Travel Demand Factors 14-2
Trip Estimates 14-2
C. CEQR Screening Analyses 14-4
Level 1 Screening Analysis Results 14-4
Level 2 Screening Analysis Results 14-5
D. Transportation Analysis Methodology 14-7
Traffic 14-7
Pedestrian Operations 14-8
Vehicular and Pedestrian Safety Evaluation 14-9
Parking Conditions Assessment 14-11
E. Traffic Analysis 14-11
2011 Existing Conditions 14-11
2014 No Build Condition 14-14
2014 Build Condition 14-15

F. Transit Analysis 14-20
Transit Study Areas 14-20
G. Pedestrian Analysis 14-21
Pedestrian Study Areas 14-21
2011 Existing Conditions 14-21
2014 No Build Condition 14-23
2014 Build Condition 14-25
H. Vehicular and Pedestrian Safety 14-27
St. Nicholas Avenue and West 125th Street 14-29
Seventh Avenue and West 125th Street 14-30
Lenox Avenue and West 125th Street 14-30
I. Parking Analysis 14-31
2011 Existing Conditions 14-31
2014 No Build Condition 14-31
2014 Build Condition 14-31
J. Traffic Mitigation 14-35

15: Air Quality 15-1
A. Introduction 15-1
Principal Conclusions 15-1
B. Methodology for Predicting Pollutant Concentrations 15-1
CEQR Technical Manual HVAC Screening Analysis 15-2
Aerscreen Analysis 15-2
Additional Sources 15-4
C. Probable Impacts of the Proposed Project 15-5
CEQR Technical Manual HVAC Screening Analysis 15-5
Aerscreen Analysis 15-5

16: Greenhouse Gas Emissions 16-1
A. Introduction 16-1
Principal Conclusions 16-1
B. Policy, Regulations, Standards, and Benchmarks for Reducing GHG Emissions 16-2
C. Methodology 16-4
Pollutants of Concern 16-4
Building Operational Emissions 16-5
Mobile Source Emissions 16-6
Construction Emissions 16-7
Emissions from Solid Waste Management 16-7
D. GHG Emissions With the Proposed Project 16-7
Building Operational Emissions 16-7
Mobile Source Emissions 16-8
Construction Emissions 16-8
Emissions from Solid Waste Management 16-8
Summary 16-8
E. Elements of the Proposed Project That Would Reduce GHG Emissions 16-9
Build Efficient Buildings 16-9
Use Clean Power 16-9
Transit-Oriented Development and Sustainable Transportation 16-10

Direct Construction Emissions 16-10
Building Materials 16-10
Conclusion 16-10

17: Noise 17-1
A. Introduction 17-1
Principal Conclusions 17-1
B. Acoustical Fundamentals 17-1
"A"-Weighted Sound Level—db(A) 17-1
Sound Level Descriptors 17-2
C. Noise Standards and Criteria 17-3
New York CEQR Noise Criteria 17-3
D. Noise Prediction Methodology 17-3
E. Existing Conditions 17-4
Equipment Used During Noise Monitoring 17-4
F. Future Noise Levels 17-5
G. Noise Attenuation Measures 17-6

18: Public Health 18-1

19: Neighborhood Character 19-1
A. Introduction 19-1
Principal Conclusions 19-1
B. Analytical Framework 19-2
C. Methodology 19-2
Neighborhood Character Components 19-2
Study Area 19-3
D. Existing Conditions 19-4
Project Site 19-4
Study Area 19-4
E. The Future Without the Proposed Project 19-5
Project Site 19-5
Study Area 19-5
F. Probable Impacts of the Proposed Project 19-6
Project Site 19-6
Study Area 19-7
G. Conclusion 19-8

20: Construction 20-1
A. Introduction 20-1
Principal Conclusions 20-1
B. Description of Construction Activities 20-1
Construction Phasing and Schedule 20-2
Construction Methods and Activities 20-2
General Construction Practices 20-6
C. The Future Without the Proposed Project 20-8
D. Probable Impacts of the Proposed Project 20-8
Transportation 20-8

Air Quality 20-9
Noise 20-10
Other Technical Areas 20-12
Rodent Control 20-14

21: Alternatives 21-1
A. Introduction 21-1
B. No Action Alternative 21-2
Description of the No Action Alternative 21-2
No Action Alternative Compared With the Proposed Project 21-2
C. No Unmitigated Significant Adverse Impact Alternatives 21-10
Scenario 1: Retention and Reuse Without Overbuild 21-11
Scenario 2: Construct New Program Above the North Building 21-12

22: Mitigation 22-1
A. Introduction 22-1
B. Historic and Cultural Resources 22-1
Summary of Proposed Mitigation Measures 22-2
C. Traffic Mitigation 22-2

23: Unavoidable Significant Adverse Impacts 23-1

24: Growth-Inducing Aspects of the Proposed Action 24-1

25: Irreversible and Irretrievable Commitments of Resources 25-1

APPENDICES (CD-ONLY)

Appendix A, "Correspondence"

Appendix B, "Historic Resources"

List of Tables

1-1 Program Components for Analysis 1-4
2-1 Study Area Zoning Districts 2-5
5-1 2014 Future With the Proposed Project: Open Space Ratios Summary 5-1
5-2 Existing Residential Population 5-6
5-3 Study Area Open Space Inventory 5-7
5-4 Existing Conditions: Adequacy of Open Space Resources 5-9
5-5 Future Without the Proposed Project: Adequacy of Open Space Resources 5-10
5-6 Future With the Proposed Project: Adequacy of Open Space Resources 5-10
5-7 2015 Future With the Proposed Project: Open Space Ratios Summary 5-12
12-1 Estimated Solid Waste Generation 12-1
13-1 Estimated Operational Energy Demand (Million BTU Per Year) 13-1
14-1 Trip Generation Factors 14-3
14-2 Trip Generation Summary 14-4
14-3 LOS Criteria for Signalized Intersections 14-7
14-4 Level of Service Criteria for Pedestrian Elements 14-9
14-5 Significant Impact Guidance for Sidewalks 14-10
14-6 Significant Impact Guidance for Corners and Crosswalks 14-10
14-7 2011 Existing Conditions Level of Service Analysis 14-13
14-8 No Build Projects 14-14
14-9 2014 No Build Condition Level of Service Analysis 14-16
14-10 2014 No Build Vs. Build Conditions Level of Service Analysis 14-18
14-11 NYCT Local Bus Routes Serving the Study Area 14-21
14-12 2011 Existing Conditions Sidewalk Analysis 14-22
14-13 2011 Existing Conditions Corner Analysis 14-23
14-14 2011 Existing Conditions Crosswalk Analysis 14-23
14-15 2014 No Build Condition Sidewalk Analysis 14-24
14-16 2014 No Build Condition Corner Analysis 14-24
14-17 2014 No Build Condition Crosswalk Analysis 14-25

14-18 2014 Build Condition Sidewalk Analysis 14-26
14-19 2014 Build Condition Corner Analysis 14-26
14-20 2014 Build Condition Crosswalk Analysis 14-27
14-21 Accident Summary 14-27
14-22 Vehicle and Pedestrian Accident Details 14-28
14-23 Summary of On-Street Parking Regulations 14-32
14-24 2011 Existing Conditions Public Parking Utilization 14-33
14-25 2011 Existing and 2014 No Build Conditions Public Parking Utilization 14-34
14-26 Proposed Project Incremental Parking Demand—Weekday 14-34
14-27 Proposed Project Incremental Parking Demand—Saturday 14-35
14-28 Recommended Traffic Mitigation Measures 14-35
14-29 2014 No Build, Build, and Build With Mitigation Conditions Level of Service Analysis . 14-35
15-1 HVAC Emission Rates and Stack Parameters 15-3
15-2 Maximum Modeled Pollutant Concentration (in $\mu g/m^3$) 15-5
16-1 Global Warming Potential (GWP) for Major GHGs 16-5
16-2 Building Floor Area and Type for GHG Analysis 16-6
16-3 Annual Vehicle Miles Traveled 16-7
16-4 Building Operational Emissions 16-7
16-5 Mobile Source Emissions (Metric Tons CO_2e) 16-8
16-6 Summary of Proposed Project's Annual GHG Emissions 2014 (Metric Tons CO_2e) . 16-8
17-1 Common Noise Levels 17-2
17-2 Average Ability to Perceive Changes in Noise Levels 17-2
17-3 Required Attenuation Values to Achieve Acceptable Interior Noise Levels 17-3
17-4 Existing Noise Levels, in db(A) 17-5
17-5 Playground Noise Analysis, in db(A) 17-5
17-6 Future Noise Levels 17-6
17-7 CEQR Attenuation Requirements 17-6
20-1 Conceptual Construction Schedule 20-2
20-2 Construction Oversight in New York City 20-7
22-1 Recommended Traffic Mitigation Measures 22-3
22-2 2014 No Build, Build, and Build With Mitigation Conditions LOS 22-4

List of Figures

Following page:

S-1 Project Location S-2
S-2 Project Site S-2
S-3 Illustrative North-South Building Section S-2
S-4 Proposed West 125th Street Facade S-2
S-5 Illustrative First Floor Plan S-2
1-1 Project Location 1-2
1-2 Project Site 1-2
1-3 Illustrative North-South Building Section 1-4
1-4 Illustrative First Floor Plan 1-4
1-5 Illustrative Rendering of Restored Historic Foyer and Staircase 1-4
1-6 Proposed West 125th Street Facade 1-4
1-7 Illustrative West 126th Street Facade 1-4
2-1 Existing Land Use 2-2
2-2 Zoning 2-4
5-1 Open Space Study Area 5-4
5-2 Open Space Resources 5-6
6-1 Tier 1 & Tier 2 Assessments 6-10
6-2 Tier 3 Assessment 6-10
6-3 Three-Dimensional Computer Model for Detailed Analysis 6-10
6-4 March 21/Sept 21 - 10:30 AM 6-10
6-5 March 21/Sept 21 - 11:30 AM 6-10
6-6 March 21/Sept 21 - 12:00 PM 6-10
6-7 March 21/Sept 21 - 1:00 PM 6-10
6-8 March 21/Sept 21 - 4:00 PM 6-10
6-9 May 6/August 6 - 11:00 AM 6-10
6-10 May 6/August 6 - 12:30 PM 6-10
6-11 May 6/August 6 - 4:00 PM 6-10

6-12 June 21 - 1:30 PM 6-10
6-13 June 21 - 4:30 PM 6-10
6-14 December 21 - 11:00 AM 6-10
6-15 December 21 - 12:00 PM 6-10
6-16 December 21 - 1:30 PM 6-10
6-17 December 21 - 2:30 PM 6-10
7-1 Historic and Cultural Resources Reference Map 7-4
7-2 Victoria Theater 7-4
7-3 Victoria Theater - South Building 7-4
7-4 Victoria Theater - South and North Buildings 7-4
7-5 Victoria Theater - North Buildings 7-4
7-6 Victoria Theater - North Buildings 7-4
7-7 Victoria Theater - North Buildings 7-4
7-8 Known Architectural Resources in Study Area 7-8
7-9 Known Architectural Resources in Study Area 7-8
7-10 Known Architectural Resources in Study Area 7-8
7-11 Known and Potential Architectural Resources in Study Area 7-10
7-12 Proposed West 125th Street Facade 7-14
7-13 Illustrative Rendering of Proposed Project, Birdseye View 7-14
7-14 View North to West 126th Street from Within Restored South Building Lobby 7-14
7-15 Illustrative Rendering of Restored Historic Foyer and Staircase 7-14
7-16 Illustrative First Floor Plan 7-14
7-17 Proposed West 126th Street Facade 7-14
8-1 Urban Design and Visual Resources Reference Map 8-4
8-2 Photographs of Project Site, Views 1 and 2 8-4
8-3 Photographs of Study Area, View 3 8-4
8-4 Photographs of Study Area, Views 4 and 5 8-4
8-5 Photographs of Study Area, Views 6 and 7 8-6
8-6 Photographs of Study Area, Views 8 and 9 8-6
8-7 Photographs of Study Area, View 10 8-6
8-8 Photographs of Study Area, View 11 8-6
8-9 Photographs of Study Area, View 12 8-6
8-10 Photographs of Study Area, View 13 8-6

8-11 Photographs of Study Area, Views 14 and 15 8-6
8-12 Photographs of Study Area, View 16 8-6
8-13 Photographs of Study Area, View 17 8-8
8-14 Photographs of Study Area, View 18 8-8
8-15 Photographs of Study Area, View 19 8-8
8-16 Proposed West 125th Street Facade....8-8
8-17 Illustrative Rendering of Proposed Project, Birdseye View 8-8
8-18 Illustrative North-South Building Section 8-8
8-19 Illustrative First Floor Plan 8-8
8-20 Illustrative West 126th Street Facade 8-8
14-1 Project Generated Traffic Volumes AM Peak Hour....14-6
14-2 Project Generated Traffic Volumes Midday Peak Hour....14-6
14-3 Project Generated Traffic Volumes PM Peak Hour....14-6
14-4 Project Generated Traffic Volumes Saturday Peak Hour 14-6
14-5 Project Generated Pedestrian Volumes AM Peak Hour 14-6
14-6 Project Generated Pedestrian Volumes Midday Peak Hour 14-6
14-7 Project Generated Pedestrian Volumes PM Peak Hour 14-6
14-8 Project Generated Pedestrian Volumes Saturday Peak Hour....14-6
14-9 Traffic Study Area 14-12
14-10 Existing Traffic Volumes AM Peak Hour 14-14
14-11 Existing Traffic Volumes Midday Peak Hour 14-14
14-12 Existing Traffic Volumes PM Peak Hour....14-14
14-13 Existing Traffic Volumes Saturday Peak Hour....14-14
14-14 2014 No Build Traffic Volumes AM Peak Hour....14-16
14-15 2014 No Build Traffic Volumes Midday Peak Hour....14-16
14-16 2014 No Build Traffic Volumes PM Peak Hour....14-16
14-17 2014 No Build Traffic Volumes Saturday Peak Hour 14-16
14-18 2014 Build Traffic Volumes AM Peak Hour....14-18
14-19 2014 Build Traffic Volumes Midday Peak Hour....14-18
14-20 2014 Build Traffic Volumes PM Peak Hour 14-18
14-21 2014 Build Traffic Volumes Saturday Peak Hour....14-18
14-22 Subway and Local Bus Service....14-20
14-23 Existing Pedestrian Volumes AM Peak 15 Minutes....14-22

14-24 Existing Pedestrian Volumes Midday Peak 15 Minutes 14-22
14-25 Existing Pedestrian Volumes PM Peak 15 Minutes 14-22
14-26 Existing Pedestrian Volumes Saturday Peak 15 Minutes..... 14-22
14-27 2014 No Build Pedestrian Volumes AM Peak 15 Minutes 14-22
14-28 2014 No Build Pedestrian Volumes Midday Peak 15 Minutes 14-24
14-29 2014 No Build Pedestrian Volumes PM Peak 15 Minutes..... 14-24
14-30 2014 No Build Pedestrian Volumes Saturday Peak 15 Minutes 14-24
14-31 2014 Project Generated Pedestrian Volumes AM Peak 15 Minutes 14-26
14-32 2014 Project Generated Pedestrian Volumes Midday Peak 15 Minutes 14-26
14-33 2014 Project Generated Pedestrian Volumes PM Peak 15 Minutes..... 14-26
14-34 2014 Project Generated Pedestrian Volumes Saturday Peak 15 Minutes 14-26
14-35 2014 Build Pedestrian Volumes AM Peak 15 Minutes..... 14-26
14-36 2014 Build Pedestrian Volumes Midday Peak 15 Minutes..... 14-26
14-37 2014 Build Pedestrian Volumes PM Peak 15 Minutes 14-26
14-38 2014 Build Pedestrian Volumes Saturday Peak 15 Minutes 14-26
14-39 On-Street Parking Regulations..... 14-32
14-40 Off-Street Parking Facilities..... 14-32
17-1 Noise Receptor Locations 17-4

✷